



P.O. BOX 1276
 CENTERVILLE, UT 84014
 801-294-9180

Estimate

ADDRESS

Johnny Johnson
 Utah Transit Authority
 669 W 200 S
 SLC, UT 84101 USA

ESTIMATE # 1024

DATE 07/19/2024

EXPIRATION DATE 09/30/2024

P.O. NUMBER

MA3225

JOB SITE

1110 S Geneva Rd Orem, UT 84059

DESCRIPTION	QTY	RATE	AMOUNT
Fireguard U.L. 2085 Listed AST 6K Gallons split 2k/4k, on two saddles, interior bare, exterior white polyurethane. Includes freight from California as well as a crane and labor to offload and set in place.	1	72,660.00	72,660.00
12.5'x 23' concrete containment with 4' high walls 8" thick (only three sides) , 2' in ground/2'above grade. (2)-6x10x18" thick footings for tank, sloped floor inside containment with a 18"x18" Catch basin to pump out of and water stop/caulked joints. Also includes 8"thick concrete 4' around outside walls to patch back into parking lot.	1	80,690.00	80,690.00
Dismantle/Cleaning and Disposal of old tanks. (excludes piping in trench)	1	11,300.00	11,300.00
Concrete containment/trench demo. Includes demo, disposal, transportation, of concrete in old AST area as well as trench. Includes disposal of piping inside trench up to building foundation. Work stops at building penetration. (Assumes nothing thicker than 12") Includes backfill up to 550 tons of state spec road base and compaction in 12" lifts of excavated containment area as well as trench. Also includes concrete pavement of up to an area 30'x40' and an area 6'x120' x 8" thick with #4 bar 18"o.c. and a 4500 psi mix.	1	93,750.00	93,750.00

****Exclusions**** Any and all tank fittings/accessories/piping/electrical work, Catwalks on new tank/ incorporation/fabrication/relocation of stairs on existing tank. Any and all bollards, repair of any unidentified utilities. Any treatment of

DESCRIPTION	QTY	RATE	AMOUNT
-------------	-----	------	--------

contaminated ground water/soil. Any engineered plans or permits if required.

	TOTAL		\$258,400.00
--	-------	--	---------------------

Accepted By

Accepted Date